

Sika Australia Pty Ltd, Wetherill Park
Emission Testing Report
Report Number R014740

Document Information

Template Version 130223

Client Name: Sika Australia Pty Ltd
Report Number: R014740
Date of Issue: 14 August 2023
Attention: Tanya Ballantyne
Address: 55 Elizabeth St
Wetherill Park NSW 2164
Testing Laboratory: Ektimo Pty Ltd, ABN 86 600 381 413

Report Authorisation



Steven Cooper
Senior Air Monitoring
Consultant

NATA Accredited Laboratory
No. 14601

Accredited for compliance with ISO/IEC 17025 - Testing. NATA is a signatory to the ILAC mutual recognition arrangement for the mutual recognition of the equivalence of testing, calibration and inspection reports.

This document is confidential and is prepared for the exclusive use of Sika Australia Pty Ltd and those granted permission by Sika Australia Pty Ltd. The report shall not be reproduced except in full.

Please note that only numerical results pertaining to measurements conducted directly by Ektimo are covered by Ektimo's terms of NATA accreditation as described in the Test Methods table. This does not include calculations that use data supplied by third-parties, comments, conclusions, or recommendations based upon the results. Refer to 'Test Methods' for full details of testing covered by NATA accreditation.

Table of Contents

1	Executive Summary	4
1.1	Background	4
1.2	Project Objective & Overview	4
1.3	Licence Comparison	4
2	Results	5
2.1	EPA 1 – Concrete Powders Stack	5
3	Plant Operating Conditions	6
4	Test Methods.....	6
5	Quality Assurance/Quality Control Information	6
6	Definitions	7
7	Appendix 1: Site Images	8

1 Executive Summary

1.1 Background

Ektimo was engaged by Sika Australia Pty Ltd to perform emission testing at their Wetherill Park plant. Testing was carried out in accordance with Environment Protection Licence (EPL) 6459.

1.2 Project Objective & Overview

The objective of the project was to conduct a monitoring programme to quantify emissions from one discharge point to determine compliance with Sika Australia Pty Ltd's Environmental Licence.

Monitoring was performed as follows:

Location	Test Date	Test Parameters*
EPA 1 – Concrete Powders Stack	5 May 2023	Solid particles

* Flow rate, velocity, temperature and moisture were also determined.

All results are reported on a dry basis at STP.

Plant operating conditions have been noted in the report.

1.3 Licence Comparison

The following licence comparison table shows that all analytes highlighted in green are within the licence limit set by the NSW EPA as per licence 6459 (last amended on 28 April 2015).

EPA	Location Description	Unit of Measure	Parameter	Licence Limit	Detected Values 05/05/2023
1	Concrete Powders Stack	milligrams per cubic meter (mg/m ³)	Solid Particles	40	7.4

Please note that the measurement uncertainty associated with the test results was not considered when determining whether the results were compliant or non-compliant.

Refer to the Test Methods table for the measurement uncertainties.

2 Results

2.1 EPA 1 – Concrete Powders Stack

Date	5/05/2023	Client	Sika Australia
Report	R014740	Stack ID	EPA 1 - Concrete Powders Stack
Licence No.	6459	Location	Wetherill Park
Ektimo Staff	Steven Cooper	State	NSW
Process Conditions	Please refer to client records.		

230424

Sampling Plane Details

Sampling plane dimensions	375 mm
Sampling plane area	0.11 m ²
Sampling port size, number & depth	2" Flange (x2), 70 mm
Duct orientation & shape	Vertical Circular
Downstream disturbance	Exit 1.5 D
Upstream disturbance	Bend 2.5 D
No. traverses & points sampled	2 12
Sample plane conformance to AS 4323.1	Conforming but non-ideal

Comments

The discharge is assumed to be composed of dry air and moisture

The sampling plane is deemed to be non-ideal due to the following reasons:

The sampling plane is too near to the downstream disturbance but is greater than or equal to 1D

The sampling plane is too near to the upstream disturbance but is greater than or equal to 2D

Stack Parameters

Moisture content, %v/v	1.1	
Gas molecular weight, g/g mole	28.8 (wet)	29.0 (dry)
Gas density at STP, kg/m ³	1.29 (wet)	1.29 (dry)
Gas density at discharge conditions, kg/m ³	1.21	

Gas Flow Parameters

Flow measurement time(s) (hhmm)	0935 & 1055
Temperature, °C	21
Temperature, K	294
Velocity at sampling plane, m/s	23
Volumetric flow rate, actual, m ³ /s	2.6
Volumetric flow rate (wet STP), m ³ /s	2.4
Volumetric flow rate (dry STP), m ³ /s	2.4
Mass flow rate (wet basis), kg/hour	11000

Isokinetic Results

Sampling time	Results	
	0943-1045	
	Concentration mg/m ³	Mass Rate g/min
Solid Particles	7.4	1.1
Isokinetic Sampling Parameters		
Sampling time, min	60	
Isokinetic rate, %	102	
Gravimetric analysis date (total particulate)	12-05-2023	

3 Plant Operating Conditions

See Sika Australia Pty Ltd records for complete process conditions. Sika personnel confirmed that production on that day is considered normal.

4 Test Methods

All sampling and analysis performed by Ektimo unless otherwise specified. Specific details of the methods are available upon request.

Parameter	Sampling method	Analysis method	Uncertainty*	NATA accredited	
				Sampling	Analysis
Sampling points - Selection	NSW EPA TM-1 (AS 4323.1)	NA	NA	✓	NA
Flow rate, temperature & velocity	NSW EPA TM-2 (USEPA Method 2)	NSW EPA TM-2 (USEPA Method 2)	8%, 2%, 7%	NA	✓
Moisture content	NSW EPA TM-22 (USEPA Method 4)	NSW EPA TM-22 (USEPA Method 4)	8%	✓	✓
Solid particles (total)	NSW EPA TM-15 (AS 4323.2)	NSW EPA TM-15 (AS 4323.2)	3%	✓	✓ ^{††}

230320

* Uncertainties cited in this table are estimated using typical values and are calculated at the 95% confidence level (coverage factor = 2).

†† Gravimetric analysis conducted at the Ektimo NSW laboratory.

5 Quality Assurance/Quality Control Information

Ektimo is accredited by the National Association of Testing Authorities (NATA) for the sampling and analysis of air pollutants from industrial sources. Unless otherwise stated test methods used are accredited with the National Association of Testing Authorities. For full details, search for Ektimo at NATA's website www.nata.com.au.

Ektimo is accredited by NATA to ISO/IEC 17025 - Testing. ISO/IEC 17025 - Testing requires that a laboratory have adequate equipment to perform the testing, as well as laboratory personnel with the competence to perform the testing. This quality assurance system is administered and maintained by the Quality Director.

NATA is a member of APAC (Asia Pacific Accreditation Co-operation) and of ILAC (International Laboratory Accreditation Co-operation). Through mutual recognition arrangements with these organisations, NATA accreditation is recognised worldwide.

6 Definitions

The following symbols and abbreviations may be used in this test report:

% v/v	Volume to volume ratio, dry or wet basis
~	Approximately
<	Less than
>	Greater than
≥	Greater than or equal to
AS	Australian Standard
CEM/CEMS	Continuous Emission Monitoring/Continuous Emission Monitoring System
CTM	Conditional test method
D	Duct diameter or equivalent duct diameter for rectangular ducts
DECC	Department of Environment & Climate Change (NSW)
Disturbance	A flow obstruction or instability in the direction of the flow which may impede accurate flow determination. This includes centrifugal fans, axial fans, partially closed or closed dampers, louvres, bends, connections, junctions, direction changes or changes in pipe diameter.
EPA	Environment Protection Authority
FTIR	Fourier Transform Infra-red
ISC	Intersociety Committee, Methods of Air Sampling and Analysis
ISO	International Organisation for Standardisation
ITE	Individual threshold estimate
Lower bound	When an analyte is not present above the detection limit, the result is assumed to be equal to zero.
Medium bound	When an analyte is not present above the detection limit, the result is assumed to be equal to half of the detection limit.
NA	Not applicable
NATA	National Association of Testing Authorities
NT	Not tested or results not required
STP	Standard temperature and pressure. Gas volumes and concentrations are expressed on a dry basis at 0°C, at discharge oxygen concentration and an absolute pressure of 101.325 kPa, unless otherwise specified.
TM	Test method
TOC	The sum of all compounds of carbon which contain at least one carbon-to-carbon bond, plus methane and its derivatives.
USEPA	United States Environmental Protection Agency
Velocity difference	The percentage difference between the average of initial flows and after flows.
Upper bound	When an analyte is not present above the detection limit, the result is assumed to be equal to the detection limit.
95% confidence interval	Range of values that contains the true result with 95% certainty. This means there is a 5% risk that the true result is outside this range.

7 Appendix 1: Site Images



EPA 1 – Concrete Powders Stack



Ektimo

ektimo.com.au

1300 364 005

MELBOURNE (Head Office)

26 Redland Drive
Mitcham
VIC 3132
AUSTRALIA

SYDNEY

6/78 Reserve Road
Artarmon
NSW 2064
AUSTRALIA

WOLLONGONG

1/251 Princes Highway
Unanderra
NSW 2526
AUSTRALIA

PERTH

52 Cooper Road
Cockburn Central
WA 6164
AUSTRALIA

BRISBANE

3/109 Riverside Place
Morningside
QLD 4170
AUSTRALIA